



NOTES:

- 1) CONCRETE SHALL BE 3000 PSI MIN.
- 2) CHANNELS SHALL BE CONSTRUCTED TO PROVIDE SMOOTH SLOPES AND RADII TO OUTLET PIPE.
- 3) ALL PIPE CONNECTIONS SHALL BE WITH FLEXIBLE BOOTS.
- 4) BASES ARE TO BE PRECAST.

**City of
McMinnville**

**DETAIL FOR
STANDARD MANHOLE
BASE SECTION**

DATE: DECEMBER 2023

DRAWING NO. **14**